

# Project Scope

#### **Project Scope**

#### 1. New Gym Spaces ~4,300SF

- gym/storm shelter
- offices
- storage

#### 2. New Pre-K Spaces ~ 2,570SF

- o 2 classrooms
- offices
- storage
- separate entry




## Design Development Updates




#### Bond Phase II Addition - Massing




#### Site Plan



#### Floor Plans




**FIRST LEVEL** 




#### Design Goals


- Reflect The Past Look Into the Future
- The **Gym** as the Community Hub Represents
  Rockbrook
- The Anchor Of The Neighborhood
- Gathering Space Where they Meet and Interact
- Emerge from the Topography The Water





#### 'Rock in the Brook'














.

#### View from Lower Parking lot




### **ECC Entry**



#### **Exterior Materials**











Brown Anodized Window Frame

White Brick

Exposed Aggregate

Acid Etched

### **ECC Entry**




















### Schedule



EXPLORE DEVELOP DETAIL

2025																		2026							
Januai	ry			February			MAR	APR	MAY	JUN	JUL	AUG	SEP	ОСТ	NOV	DEC	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	
6-10	13-17	20-24	27-31	3-7	10-14	17-21	24-28																		
1/9																									
										Eurnit	ure Des	ian/Sal	ection I	Process	1										
								Furniture Design/Selection Process						Furniture and Equipment Procurement											
															Fullit	are and	Equipi	Herit Pi	ocuren	lent					
																				-		Furnitu	re Install		
										_															
		CITY PL	AN REV	IEW																					
																						Owne	r Move	In	
ubmitt	al - 1/17																								
		BID/PR	OCURE																						
										Construction (12 Months)															
																							1		
Ç.																	п	unch I	ist Com	pletion	5/1/26	5/31/26			
																		unch L	ist Com	pietion	3/1/20-	3/31/20			

Goal to turn over new addition project to school the summer before 2026-2027 School Year

#### **Next Steps:**

- BVH to meet with City of Omaha for Plan Review
- Student Engagement Activities: Dec 13, 2024
- DAC Meeting: Dec 19, 2024
  - Review of final design and materials
- Construction Document Due Jan 17, 2025

# Thank you!